



NOTES

1. TRENCHES MADE WITHIN 5' PARALLEL TO AN EXISTING GUTTER OR EDGE OF ROAD WILL REQUIRE REMOVAL AND REPLACEMENT OF EXISTING AC PAVING TO EDGE.
2. IF UTILITY CONFLICTS REQUIRE OFFSET OF NEW OR EXISTING WATER MAINS OR WATER SERVICES, WATER FACILITIES SHALL NOT BE INSTALLED WITH LESS THAN 2-FEET COVER.
3. POTHoles SHALL BE BACKFILLED WITH CONTROLLED DENSITY FILL INSTEAD OF CLASS II AGGREGATE BASE. SAND BEDDING SHALL STILL BE REPLACED BACK OVER WATER MAIN AS SHOWN.

CITY OF NAPA

PUBLIC WORKS - WATER DIVISION

WATER TRENCH DETAIL

DATE REVISED DECEMBER 2015

CHECKED

APPROVED

SCALE

mt

JRL

NONE

W - 13A

DWG NO.